ABC

ABC Constructions USA

Licensed, Insured & Bonded | Enterprise Exterior Solutions

🎉 50% Deposit Confirmed — Work In Progress (WIP) PJ-1001

📋 Proposal Summary

Created: 20/10/2026

CLIENT NAME

Robert Martinez

PROPERTY ADDRESS

104 Oak Ridge Dr, Austin, TX

WORK TYPE

Drainage

SALES REPRESENTATIVE

Michael Scott ((555) 302-8819)

🏗️ Scope of Work & Engineering Specifications

ABC Constructions will provide all skilled labor, specialized machinery, materials, and county permit coordination for the following specifications:

DRAINAGE SYSTEM ARCHITECTURE

- ✓ Deep trenching (18"-24") graded with laser transit at minimum 1% gravity slope.
- ✓ Heavy-duty 4" perforated smooth-wall interior PVC piping (ASTM D2729).
- ✓ 3/4" double-washed aggregate stone envelope wrapped in commercial geotextile filter fabric.
- ✓ 2× 12"x12" high-capacity catch basins with debris filters connected at primary downspouts.
- ✓ High-efficiency pop-up discharge emitter with auto-drain valve at perimeter boundary.

🏛️ COUNTY PERMITS & 811 UTILITY PROTECTION

- ✓ State & County permit filing handled directly through municipal portal.
- ✓ Jolley Co. coordination with 811 public utility providers to mark all gas, power, water & telecom lines prior to digging.
- ✓ Trench remains open for mandatory County staff inspection before final backfill closure.

💵 Investment Breakdown

DESCRIPTION	QTY/UNIT	AMOUNT
Core Materials & System Components Commercial grade piping/lighting/sod & aggregates	Lump Sum	$3570.00
Excavation, Certified Installation & Grading Skilled crew, laser slope verification & clean-up	Lump Sum	$3655.00
State Portal Permit Filing & 811 Utility Marking Jolley Co. utility ticket & county inspection oversight	1 Service	$1275.00

Total Project Value: **$8,500.00**

50% Deposit Due Today: **$4,250.00**

Remaining Balance (Due Upon County Pass): $4,250.00

🚀 Project Roadmap & Milestones

1. **Proposal Signed & 50% Deposit Confirmed**
   $4250.00 paid via Stripe Sandbox. Receipt dispatched to robert.m@example.com.
2. **State & Municipal Permitting**
   Permit filing submitted to state portal; pending clearance.
3. **811 Utility Provider Marking (Jolley Co.)**
   Utility locators marking underground power, gas, and fiber on premises.
4. **7-Day Advance Notice & On-Site Installation**
   Crew dispatched with materials. Drainage kept open for County staff inspection.
5. **Final County Pass & 24-Hour Maintenance Guide**
   Trench covered, final payment settled, and custom property maintenance guide generated.